



Member

**KESSELINSPEKTORAT
PRESSURE VESSEL INSPECTORATE**

Richtistrasse 15, CH - 8304 Wallisellen, Tel. +41 44 877 61 11

**SVTI
ASIT**

Approval

No. KIS.VZ.5200294

Scope

1. Basic principle

The Pressure Vessels Inspectorate of the SVTI, as an accredited public administrative body for the assessment of legal conformity and for the safety of pressure vessels and installations, grants the below mentioned company

Company	Novi Feromont d.o.o.
Adress	Kolodvorska 80 B
Postcode / site	HR-40320 Donji Kraljevec
Client No	0000032908
Phone No	00385/40/655333
Internet	Marketing@noviferomont.hr

the license according to the SVTI prescriptions specification 704, manufacturing of steel welding parts for the construction and initial pressure testing of pressure vessels type 4, for gas insulated switches, switchgears and transmission lines, within the delegation by SVTI.

2. Validity

This license has a validity of 3 years. It may be extended on request.

Valid until **03.06.2025**

Changes in the organization or modifications of production and testing equipment, as well as the change of responsible supervisory and inspection personnel must be notified in writing in order to be legally effective.

3. Initial approval

The initial approval was effected on 16.04.1998

5. Responsibilities Welding Operations

Test supervisor	Mr. Dario Sušec
Range of responsibilities	According to SVTI-prescription 502 Contact person for SVTI
Deputy	Mr. Krunoslav Siladi
Inspector and testers	See separate list
Welding supervision	Mr. Krunoslav Siladi
Range of responsibilities	According to SVTI prescription 503
Deputy	Mr. Mario Mirić, Zoran Sinković

6. Material

In accordance to SVTI Prescriptions, specification 704F.

7. Approvals

Non-destructive testing

- PT, UT, VT qualification according ISO9712
- RT tests are carried out from an external company
- Initial pressure test according SVTI specification 704

8. Special Regulations

- Construction- and pressure tests acc. to the SVTI prescription, specification 704, number 15
- At least one construction part per standard type of the production series of every installation has to be tested by the SVTI resp. the TÜV SAVA
- The other parts of the production series may be tested and approved by the competent tester of the manufacturing plant by delegation of the SVTI.
- The competent tester of the manufacturer plant puts his stamp on the components as evidence of the successfully passed tests.
- The manufacturer establishes the final documentation including all the series of the installation with indication of the SVTI installation number.
- Based on the present documentation, the SVTI establishes an overall certification for the series and the installation
- The admission of the standard type of the components is effected by the SVTI.
- Each part of a pressure vessel with casting components has to be submitted to a burst

9. Operational installations

See attachment

10. Testing installations

See attachment

11. Test and inspection prescriptions

SVTI prescription volume 1, specification 704, Rev. 1.04

12. Plant visit by an inspector / expert

The plant visit was performed on 09.06.2022 by Mrs. Angela Klamt.

14. Attachment

Organigram

Example of an approval concerning the construction- and initial pressure test

List of stamps from competent persons and functional matrix

List of the competent testers

List of approved welder and welding procedures (WPQR)

List of NDT persons for inspection of pressurized steel constructions (VT, PT, UT)

List of main manufacturing and testing equipment

Confirmation (ISO 9001/14001:2015, ISO 45001:2018)

Certificate ISO 3834-2

Wallisellen, 6.20.2022

Vessel Inspectorate
Construction

Angela Klamt

Summary of specification 704 for construction and first pressure testing in delegation of SVTI

Principles:

- The special permission for the construction and first pressure testing in delegation of the SVTI has a validity of 3 years. It can be extended to request and withdrawn with abuses.
- Each SF6 component / cast piece must be submitted to the licensing procedure.
- With each cast piece, a burst test must be accomplished, respectable computations must be present.
- Each component must be submitted in the routine pressure test, with exception of the parts with limited accountability.
- Each component cast piece, sheet metals, soils, connecting piece and flanges must be supplied with a 3.1 certificate of acceptance test, with exception of the parts with limited accountability.
- Each cast piece component must be marked concerning the material, batch number of the foundry and examined condition.
- Each cast piece must, for the indication of the existed construction and first pressure testing, be marked with the production-no, permissible operating pressure and the tester stamp.
- For the components, the performed construction and first pressure testing must be certified officially.

Definitions:

- The approval of the components is performed by the SVTI.
- The burst test takes place in the presence of the SVTI (requests for partner organizations can be placed).
- Approval with burst test is valid for the model, material and the foundry.
- Approved designs have a validity of 2 years.
- Per series and installation, the construction and first pressure testing is to be accomplished with 1 piece in the presence of the SVTI / the partner organization